

To our customers,

---

## Old Company Name in Catalogs and Other Documents

---

On April 1<sup>st</sup>, 2010, NEC Electronics Corporation merged with Renesas Technology Corporation, and Renesas Electronics Corporation took over all the business of both companies. Therefore, although the old company name remains in this document, it is a valid Renesas Electronics document. We appreciate your understanding.

Renesas Electronics website: <http://www.renesas.com>

April 1<sup>st</sup>, 2010  
Renesas Electronics Corporation

Issued by: Renesas Electronics Corporation (<http://www.renesas.com>)

Send any inquiries to <http://www.renesas.com/inquiry>.

## Notice

1. All information included in this document is current as of the date this document is issued. Such information, however, is subject to change without any prior notice. Before purchasing or using any Renesas Electronics products listed herein, please confirm the latest product information with a Renesas Electronics sales office. Also, please pay regular and careful attention to additional and different information to be disclosed by Renesas Electronics such as that disclosed through our website.
2. Renesas Electronics does not assume any liability for infringement of patents, copyrights, or other intellectual property rights of third parties by or arising from the use of Renesas Electronics products or technical information described in this document. No license, express, implied or otherwise, is granted hereby under any patents, copyrights or other intellectual property rights of Renesas Electronics or others.
3. You should not alter, modify, copy, or otherwise misappropriate any Renesas Electronics product, whether in whole or in part.
4. Descriptions of circuits, software and other related information in this document are provided only to illustrate the operation of semiconductor products and application examples. You are fully responsible for the incorporation of these circuits, software, and information in the design of your equipment. Renesas Electronics assumes no responsibility for any losses incurred by you or third parties arising from the use of these circuits, software, or information.
5. When exporting the products or technology described in this document, you should comply with the applicable export control laws and regulations and follow the procedures required by such laws and regulations. You should not use Renesas Electronics products or the technology described in this document for any purpose relating to military applications or use by the military, including but not limited to the development of weapons of mass destruction. Renesas Electronics products and technology may not be used for or incorporated into any products or systems whose manufacture, use, or sale is prohibited under any applicable domestic or foreign laws or regulations.
6. Renesas Electronics has used reasonable care in preparing the information included in this document, but Renesas Electronics does not warrant that such information is error free. Renesas Electronics assumes no liability whatsoever for any damages incurred by you resulting from errors in or omissions from the information included herein.
7. Renesas Electronics products are classified according to the following three quality grades: “Standard”, “High Quality”, and “Specific”. The recommended applications for each Renesas Electronics product depends on the product’s quality grade, as indicated below. You must check the quality grade of each Renesas Electronics product before using it in a particular application. You may not use any Renesas Electronics product for any application categorized as “Specific” without the prior written consent of Renesas Electronics. Further, you may not use any Renesas Electronics product for any application for which it is not intended without the prior written consent of Renesas Electronics. Renesas Electronics shall not be in any way liable for any damages or losses incurred by you or third parties arising from the use of any Renesas Electronics product for an application categorized as “Specific” or for which the product is not intended where you have failed to obtain the prior written consent of Renesas Electronics. The quality grade of each Renesas Electronics product is “Standard” unless otherwise expressly specified in a Renesas Electronics data sheets or data books, etc.
  - “Standard”: Computers; office equipment; communications equipment; test and measurement equipment; audio and visual equipment; home electronic appliances; machine tools; personal electronic equipment; and industrial robots.
  - “High Quality”: Transportation equipment (automobiles, trains, ships, etc.); traffic control systems; anti-disaster systems; anti-crime systems; safety equipment; and medical equipment not specifically designed for life support.
  - “Specific”: Aircraft; aerospace equipment; submersible repeaters; nuclear reactor control systems; medical equipment or systems for life support (e.g. artificial life support devices or systems), surgical implantations, or healthcare intervention (e.g. excision, etc.), and any other applications or purposes that pose a direct threat to human life.
8. You should use the Renesas Electronics products described in this document within the range specified by Renesas Electronics, especially with respect to the maximum rating, operating supply voltage range, movement power voltage range, heat radiation characteristics, installation and other product characteristics. Renesas Electronics shall have no liability for malfunctions or damages arising out of the use of Renesas Electronics products beyond such specified ranges.
9. Although Renesas Electronics endeavors to improve the quality and reliability of its products, semiconductor products have specific characteristics such as the occurrence of failure at a certain rate and malfunctions under certain use conditions. Further, Renesas Electronics products are not subject to radiation resistance design. Please be sure to implement safety measures to guard them against the possibility of physical injury, and injury or damage caused by fire in the event of the failure of a Renesas Electronics product, such as safety design for hardware and software including but not limited to redundancy, fire control and malfunction prevention, appropriate treatment for aging degradation or any other appropriate measures. Because the evaluation of microcomputer software alone is very difficult, please evaluate the safety of the final products or system manufactured by you.
10. Please contact a Renesas Electronics sales office for details as to environmental matters such as the environmental compatibility of each Renesas Electronics product. Please use Renesas Electronics products in compliance with all applicable laws and regulations that regulate the inclusion or use of controlled substances, including without limitation, the EU RoHS Directive. Renesas Electronics assumes no liability for damages or losses occurring as a result of your noncompliance with applicable laws and regulations.
11. This document may not be reproduced or duplicated, in any form, in whole or in part, without prior written consent of Renesas Electronics.
12. Please contact a Renesas Electronics sales office if you have any questions regarding the information contained in this document or Renesas Electronics products, or if you have any other inquiries.

(Note 1) “Renesas Electronics” as used in this document means Renesas Electronics Corporation and also includes its majority-owned subsidiaries.

(Note 2) “Renesas Electronics product(s)” means any product developed or manufactured by or for Renesas Electronics.

# SH7086 CPU Board M3A-HS86

User's Manual

Renesas 32-Bit RISC Microcomputers  
SuperH™ RISCengine Family / SH7080 Group

Microsoft, MS-DOS, Windows and Windows.NET are registered trademarks of Microsoft Corporation of the U.S. in the U.S. and other countries.

IBM and AT are registered trademarks of International Business Machines Corporation of the U.S.

Adobe and Acrobat are registered trademarks of Adobe Systems Incorporated.

All other brand names and product names are registered trademarks or trademarks of the respective proprietors.

#### Requests for Safety Design

- Renesas is constantly making efforts to improve the quality and reliability of its products. However, not all semiconductor products are trouble-free, they may become faulty or operate erratically. To ensure that no accidents such as injury or a fire or no social damage may arise from Renesas semiconductor products should they become faulty or operate erratically, please pay careful attention to the safety design of your system by, for example, considering redundancy design and incorporating measures to check the spread of a fire and prevent device malfunction.

#### Precautions on Using This Manual

- This manual only provides reference information to help customers purchase the appropriate type of Renesas Technology product that suits the intended purpose of use, and the technical information contained herein does not implicitly or otherwise grant a license or rights to use the intellectual property or other rights of Renesas Technology.
- Renesas Technology will not assume any responsibility for damage or losses or infringement on the third parties' rights arising from the use of product data, diagrams, tables, programs, algorithms or example application circuits presented in this manual.
- The product data, diagrams, tables, programs, algorithms and all other information presented herein reflect the latest that was available at the time this manual was issued, and Renesas Technology reserves the right to change the products or specifications described herein without prior notice. When purchasing Renesas Technology semiconductor products, please contact Renesas Technology or Renesas Technology Sales or other distributors to obtain the latest information, and also keep abreast of the information published at the Renesas Technology home page (<http://www.renesas.com>) or through other media.
- The information contained herein was carefully prepared and is believed to be correct. However, Renesas Technology will not assume responsibility for losses that the customers by any possibility may suffer because of erroneous description in this manual.
- To use the technical contents in product data, diagrams or tables or the programs or algorithms presented herein for your system, please carefully evaluate their suitability as part of the entire system, not singly as a technical content, program or algorithm alone, to determine in advance whether they are actually suitable for your system. Renesas Technology will not assume responsibility for the suitability of said items in user systems.
- The products presented herein are not designed or manufactured for use in equipment or systems that are used under conditions where human life is concerned. If you plan to use the products presented herein for special applications such as transportation, mobile, medical, aerospace, nuclear control or submarine repeater equipment or systems, please consult Renesas Technology or Renesas Technology Sales or other distributors.
- This manual may not be copied or reproduced, in whole or part, without prior written consent of Renesas Technology.
- For more detailed information or for questions or doubts about this manual, please consult Renesas Technology or Renesas Technology Sales or other distributors.



# Table of Contents

Chapter1 Overview.....	1-1
1.1 Overview .....	1-2
1.2 Configuration .....	1-2
1.3 External Specifications .....	1-3
1.4 External View .....	1-4
1.5 M3A-HS86 Block Diagram.....	1-5
1.6 M3A-HS86 Board Overview .....	1-6
1.7 M3A-HS86 Memory Mapping .....	1-8
1.8 Absolute Maximum Ratings.....	1-11
1.9 Recommended Operating Conditions .....	1-11
Chapter2 Functional Overview .....	2-1
2.1 Functional Overview .....	2-2
2.2 CPU.....	2-3
2.3 Memory .....	2-4
2.3.1 SH7086 On-chip Memory.....	2-4
2.3.2 SDRAM .....	2-4
2.3.3 Expand of Flash Memory .....	2-7
2.4 Serial Port Interface.....	2-8
2.5 I/O Ports .....	2-9
2.6 Power Supply Circuit .....	2-13
2.7 Clock Module.....	2-14
2.8 Reset Module .....	2-15
2.9 Interrupt Switches.....	2-16
2.10 E10A-USB Interface .....	2-17
Chapter 3 Operational Specifications .....	3-1
3.1 M3A-HS86 Connectors Outline .....	3-2
3.1.1 H-UDI Connector (J1,J2).....	3-3
3.1.2 Serial Port Connector (J3).....	3-5
3.1.3 External Power Supply Connectors for the SH7086 (J4) .....	3-6
3.1.4 Power Supply Connector (J5) .....	3-7
3.1.5 User I/O Connector (J6-J8) .....	3-8
3.1.6 Extension Connectors (J9-J13) .....	3-10
3.1.7 Extension Connector (J14).....	3-16
3.2 Outline of Switches and LEDs .....	3-17
3.2.1 SH7086 Power Supply Select Jumpers (JP1) .....	3-18
3.2.2 FWE Pin Select Jumper (JP2).....	3-19
3.2.3 Switch and LED Functions .....	3-20
3.3 Board Dimensions of M3A-HS86.....	3-22
Appendix .....	A-1

## M3A-HS86 SCHEMATICS

## Chapter1

---

### Overview

## 1.1 Overview

The M3A-HS86 is the CPU board designed for users to evaluate the functionality and performance of the SH7086 group of Renesas Technology original microcomputers, as well as develop and evaluate the application software for this group of microcomputers. The SH7086's data bus, address bus and various internal peripheral circuit function pins are connected to the extension connector of the M3A-HS86, allowing users to evaluate the timing relationship with peripheral devices using measurement instruments or develop extension boards tailored to suit development purposes. Furthermore, the E10A-USB or the on-chip emulator made by Renesas Technology can also be connected to the M3A-HS86.

## 1.2 Configuration

Figure1.2.1 shows an example of system configuration using the M3A-HS86.




Figure1.2.1 System Configuration Example of M3A-HS86



## 1.3 External Specifications

Table1.3.1 lists external specifications of M3A-HS86.

Table1.3.1 External Specifications of M3A-HS86

No.	Item	Content
1	CPU	SH7086 <ul style="list-style-type: none"> <li>● Input(XIN) clock : 10MHz</li> <li>● Bus clock : 40MHz,max</li> <li>● CPU clock : 80MHz,max</li> <li>● On-chip memory</li> <li>Flash memory : 512KB</li> <li>RAM : 32KB</li> </ul>
2	Memory *M3A-HS86(3.3V version) only	<ul style="list-style-type: none"> <li>● SDRAM : 16 Mbytes.(16-bit bus width) 1pc</li> <li>● External flash memory enabled to mount</li> </ul>
3	Connectors	<ul style="list-style-type: none"> <li>● Extension connector (Bus, I/O, VCC, GND)</li> <li>● User I/O connector (SH7086's MTU2 and A/D function pins)</li> <li>● Serial port connector (D-sub 9pins)</li> <li>● H-UDI connector (36pins)</li> <li>● H-UDI connector (14pins)</li> </ul>
4	LED	<ul style="list-style-type: none"> <li>● POWER LED (1pc.)</li> <li>● LED for interrupt switch (1pc.)</li> <li>● User LED (7pcs.)</li> </ul>
5	Switches	<ul style="list-style-type: none"> <li>● Reset switch (1pc.)</li> <li>● NMI switch (1pc.)</li> <li>● IRQ1 switch (1pc.)</li> <li>● DIP switch for system setting (1pc.,4 poles)</li> <li>● DIP switch for users (1pc.,4 poles)</li> </ul>
6	Package Dimensions	<ul style="list-style-type: none"> <li>● Dimensions :100mm x 100mm</li> <li>● Mounting form :6-layer, double-side mounted</li> <li>● Board configuration :1 board</li> </ul>

## 1.4 External View

Figure1.4.1 shows the external view of M3A-HS86.




Figure1.4.1 External View of M3A-HS86 (IC socket mounted version)

## 1.5 M3A-HS86 Block Diagram

Figure1.5.1 shows the system block diagram of M3A-HS86.





Figure1.5.1 System Block Diagram of M3A-HS86


## 1.6 M3A-HS86 Board Overview

Figure1.6.1 shows the M3A-HS86 board overview.

&lt; Top View of the Component Side &gt;



&lt; Top View of the Solder Side &gt;



Notes: \*1: Not mounted \*2: 3.3V version only \*3: Can be mounted only for 3.3V version

Figure1.6.1 M3A-HS86 Board Overview

Table1.6.1 lists main components mounted in the M3A-HS86.

Table1.6.1 Main Components Mounted in the M3A-HS86

Symbol	Parts Name	Remarks	Recommended parts number for not-mounted components
U1	CPU	SH7086 (Renesas)	
U1	CPU socket	NQPACK176SD	
U2	Clock buffer	Not mounted	CY2305SC-1 (Cypress)
U3	Flash memory	Not mounted (Can be mounted only for 3.3V version)	
U4	SDRAM	3.3V version only	
U5	RS-232C driver		
U6	Reset IC	M51957BFP (Renesas)	
U7	Logic IC		
U8	3.3V voltage regulator		
X1	Oscillator	10.00MHz	
J1	H-UDI connector	36-pin type	
J2	H-UDI connector	14-pin type	
J3	Serial port connector		
J4	External power supply connector	Not mounted	A2-2PA-2.54DSA (Hirose)
J5	Power supply connector		
J6	User I/O connector	Not mounted	XG4C-2634 (Omron)
J7,J8	User I/O connector	Not mounted	A2-3PA-2.54DSA (Hirose)
J9,J11,J12	Extension connector	Not mounted	XG4C-2031 (Omron)
J10,J13	Extension connector	Not mounted	XG4C-4031 (Omron)
J14	Extension connector	Not mounted	3428-6002LCSC (Sumitomo 3M)
LED1	Power LED	Blue	
LED2-8	User LED	Green	
LED9	LED for interrupt confirmation	Red/Yellow green (Two colors)	
SW1	Power switch		
SW2	Reset switch		
SW3	DIP switch for users		
SW4	DIP switch for system setting		
SW5	NMI switch		
SW6	IRQ1 switch		
SW7	MRES switch	Not mounted	B3SN-3012 (Omron)

## 1.7 M3A-HS86 Memory Mapping

Figure1.7.1, Figure1.7.2 and Figure1.7.3 show a memory mapping example of SH7086 in the M3A-HS86.




Figure1.7.1 Memory Mapping Example of SH7086 (MCU mode 3)

Logical space of the SH7086 MCU mode 0,1 (On-chip ROM disabled mode)		Memory Mapping of the M3A-HS86	
H'0000 0000	CS0 space: 64MB	H'0000 0000	Flash Memory (8MB) *1
H'03FF FFFF		H'007F FFFF	User Area
H'0400 0000	CS1 space: 64MB	H'03FF FFFF	User Area
H'07FF FFFF		H'0400 0000	
H'0800 0000	CS2 space: 64MB	H'07FF FFFF	User Area
H'0BFF FFFF		H'0800 0000	
H'0C00 0000	CS3 space: 64MB	H'0BFF FFFF	SDRAM(16MB) *2
H'0FFF FFFF		H'0C00 0000	
H'1000 0000	CS4 space: 64MB	H'0CFF FFFF	User Area
H'13FF FFFF		H'0FFF FFFF	User Area
H'1400 0000	CS5 space: 64MB	H'1000 0000	
H'17FF FFFF		H'13FF FFFF	User Area
H'1800 0000	CS6 space: 64MB	H'1400 0000	
H'1BFF FFFF		H'17FF FFFF	User Area
H'1C00 0000	CS7 space: 64MB	H'1800 0000	
H'1FFF FFFF		H'1BFF FFFF	User Area
H'2000 0000	Reserved	H'1C00 0000	
H'3FFF FFFF		H'1FFF FFFF	Reserved
H'4000 0000	CS8 space: 1GB	H'2000 0000	
H'7FFF FFFF		H'3FFF FFFF	User Area
H'8000 0000	Reserved	H'4000 0000	
H'FFF7 FFFF		H'7FFF FFFF	Reserved
H'FFF8 0000	SDRAM Mode setting	H'8000 0000	
H'FFF9 FFFF		H'FFF7 FFFF	SDRAM Mode setting
H'FFFA 0000	Reserved	H'FFF8 0000	
H'FFFF 3FFF		H'FFF9 FFFF	Reserved
H'FFFF 4000	On-chip RAM (32KB)	H'FFFA 0000	
H'FFFF BFFF		H'FFFF 3FFF	On-chip RAM (32KB)
H'FFFF C000	On-chip peripheral Module	H'FFFF 4000	
H'FFFF FFFF		H'FFFF BFFF	On-chip peripheral Module
		H'FFFF C000	
		H'FFFF FFFF	

**Notes**  
 \*1: For the case that 8MB flash memory is mounted (M3A-HS86(3.3V version) only)  
 \*2: M3A-HS86(3.3V version) only

Figure1.7.2 Memory Mapping Example of SH7086 (MCU mode 0,1)

Logical space of the SH7086 MCU mode 2 (On-chip ROM enabled mode)		Memory Mapping of the M3A-HS86	
H'0000 0000		H'0000 0000	
H'0007 FFFF	On-chip ROM (512KB)	H'0007 FFFF	On-chip ROM (512KB)
H'0008 0000	Reserved	H'0008 0000	Reserved
H'01FF FFFF		H'01FF FFFF	
H'0200 0000	CS0 space: 32MB	H'0200 0000	Flash Memory (8MB)
H'03FF FFFF		H'027F FFFF	User Area
H'0400 0000	CS1 space: 64MB	H'03FF FFFF	
H'07FF FFFF		H'0400 0000	User Area
H'0800 0000	CS2 space: 64MB	H'07FF FFFF	
H'0BFF FFFF		H'0800 0000	User Area
H'0C00 0000	CS3 space: 64MB	H'0BFF FFFF	
H'0FFF FFFF		H'0C00 0000	SDRAM(16MB) *2
H'1000 0000	CS4 space: 64MB	H'0CFF FFFF	User Area
H'13FF FFFF		H'0FFF FFFF	
H'1400 0000	CS5 space: 64MB	H'1000 0000	User Area
H'17FF FFFF		H'13FF FFFF	
H'1800 0000	CS6 space: 64MB	H'1400 0000	User Area
H'1BFF FFFF		H'17FF FFFF	
H'1C00 0000	CS7 space: 64MB	H'1800 0000	User Area
H'1FFF FFFF		H'1BFF FFFF	
H'2000 0000	Reserved	H'1C00 0000	User Area
H'3FFF FFFF		H'1FFF FFFF	
H'4000 0000	CS8 space: 1GB	H'2000 0000	Reserved
H'7FFF FFFF		H'3FFF FFFF	
H'8000 0000	Reserved	H'4000 0000	User Area
H'FFF7 FFFF		H'7FFF FFFF	
H'FFF8 0000	SDRAM Mode setting	H'8000 0000	Reserved
H'FFF9 FFFF		H'FFF7 FFFF	
H'FFFA 0000	Reserved	H'FFF8 0000	SDRAM Mode setting
H'FFFF 3FFF		H'FFF9 FFFF	
H'FFFF 4000	On-chip RAM (32KB)	H'FFFA 0000	Reserved
H'FFFF BFFF		H'FFFF 3FFF	
H'FFFF C000	On-chip peripheral Module	H'FFFF 4000	On-chip RAM (32KB)
H'FFFF FFFF		H'FFFF BFFF	
		H'FFFF C000	On-chip peripheral Module
		H'FFFF FFFF	

Notes

\*1: For the case that 8MB flash memory is mounted (M3A-HS86(3.3V version) only)

\*2: M3A-HS86(3.3V version) only

Figure1.7.3 Memory Mapping Example of SH7086 (MCU mode 2)



## 1.8 Absolute Maximum Ratings

Table1.8.1 lists the absolute maximum ratings of M3A-HS86.

Table1.8.1 Absolute Maximum Ratings of M3A-HS86

Symbol	Parameter	Rated Value	Remarks
5VCC	5V system power supply voltage	-0.3V to 6.0V	Relative to VSS
3VCC	3.3V system power supply voltage	-0.3V to 4.6V	Relative to VSS
Topr	Operating ambient temperature	-0°C to 50°C	No dewdrops allowed. Use in corrosive gas environment prohibited.
Tstr	Storage ambient temperature	-10°C to 60°C	No dewdrops allowed. Use in corrosive gas environment prohibited.

Note: The ambient temperature refers to the air temperature in places closest possible to the board.

## 1.9 Recommended Operating Conditions

Table1.9.1 lists the recommended operating conditions of M3A-HS86.

Table1.9.1 Recommended Operating Conditions of M3A-HS86

Symbol	Parameter	Rated Value	Remarks
5VCC	5V system power supply voltage	4.75V to 5.25V	Relative to VSS
3VCC	3.3V system power supply voltage	3.0V to 3.6V	Relative to VSS
-	Maximum current consumption in the board	Within 1A	
Topr	Operating ambient temperature	0°C to 50°C	No dewdrops allowed. Use in corrosive gas environment prohibited.

\* This is a blank page \*



## 2.1 Functional Overview

The M3A-HS86 is the SH7086 CPU board that has the functions listed in Table2.1.1.

Table2.1.1 lists the functional modules of M3A-HS86.

Table2.1.1 Functional Modules of M3A-HS86

Sections	Functions	Contents
2.2	CPU	SH7086 <ul style="list-style-type: none"> <li>● Input(XIN) clock : 10MHz</li> <li>● Bus clock : 40MHz,max</li> <li>● CPU clock : 80MHz,max</li> <li>● On-chip memory               <ul style="list-style-type: none"> <li>- Flash memory: 512KB</li> <li>- RAM : 32KB</li> </ul> </li> </ul>
2.3	Memory *M3A-HS86(3.3V version) only	<ul style="list-style-type: none"> <li>● SDRAM : 16 Mbytes(16-bit bus width) 1pc.</li> <li>● External flash memory enabled to mount</li> </ul>
2.4	Serial Port Interface	Connects SCI1 of the SH7086 to the Serial Port connector
2.5	I/O Ports	Connects to the input/output ports of the SH7086
2.6	Power Supply Circuit	Controls the system power supply of the M3A-HS86
2.7	Clock Module	Controls the system clock
2.8	Reset Module	Controls device reset mounted on the M3A-HS86
2.9	Interrupt Switches	Connect to the NMI and IRQ1 pins
2.10	E10A-USB Interface	SH7086 H-UDI/AUD interface
-	Operational specifications	Connectors, switches and LEDs <ul style="list-style-type: none"> <li>● SH7086 extension connector</li> <li>● Switches and LEDs</li> <li>● H-UDI connector</li> </ul> Detailed in Chapter 3.

## 2.2 CPU

The M3A-HS86 contains the 32-bit RISC microcomputer SH7086 that operates with a maximum 80MHz of CPU clock frequency. The SH7086 includes 512-Kbyte flash memory, and 32-Kbyte SRAM, making it useful in a wide range of applications from data processing to equipment control.

The M3A-HS86 can be operated with a maximum 80MHz of CPU clock frequency (external bus 40MHz, max) using a 10MHz input clock.

Figure2.2.1 shows the SH7086 block diagram in the M3A-HS86.




Figure2.2.1 SH7086 Block Diagram

## 2.3 Memory

### 2.3.1 SH7086 On-chip Memory

The SH7086 includes 512-Kbyte flash memory and 32-Kbyte SRAM.

### 2.3.2 SDRAM

The M3A-HS86 (3.3V version) mounts 16MB SDRAM as standard equipment. SDRAM is controlled by the bus state controller built into SH7086. Table2.3.1 lists SDRAM specifications used in M3A-HS86. Figure2.3.1 shows the block diagram of SDRAM connection.

Table2.3.1 SDRAM Specifications

Specifications	Contents
Configuration	16 Mbytes (16-bit bus) x 1pc.
Capacity	16 Mbytes
Access Time	5.4ns
CAS Latency	2(at 40MHz bus clock)
Refresh Interval	4,096 refresh cycles every 64ms
Row Address	A11- A0
Column Address	A8 - A0
Number of Banks	4-bank operation controlled by BA0 and BA1




Figure2.3.1 Block Diagram of SDRAM Connection

Table2.3.2 lists an example of bus state controller settings for operation with the SH7086 Bus clock at 40MHz.

Table2.3.2 Example of Bus State Controller Settings at SDRAM

User Area	SDRAM Controller Settings
CS3	<p><b>CS3 Space Bus Control Register(CS3BCR)</b>  Initial value : H'36DB 0600  Recommended set value : H'1000 4400  - Specify idle cycles between write-read cycles and write-write cycles  IWW[2:0] = 001 ; 1 idle cycle inserted  - Specify memory type : TYPE[2:0] = 100 ;SDRAM  - Data bus size : BSZ[1:0] = B'10 ;16-bit size</p> <p><b>CS3 Space Wait Control Register(CS3WCR)</b>  Initial value : H'0000 0500  Recommended set value :H'0000 4891  - Number of Auto-Precharge Completion Wait Cycles  TRP[1:0] = 10 ;3 cycles  - Wait Cycles between ACTV Command and READ(A)/WRIT(A) Command  TRCD[1:0] = 10 ;3 cycles  - Area 3 CAS latency  A3CL[1:0] = 01 ;2 cycles  - WRIT(A) command→Number of Auto-Precharge/PRE Command cycles  TRWL[1:0] = 10 ;2 cycles  - REF Command/Self-Refresh Release→Number of ACTV/REF/MRS Command cycles.  TRC[1:0] = 01 ; 4 cycles</p> <p><b>SDRAM Control Register(SDCR)</b>  Initial value : H'0000 0000  Recommended set value : H'0000 0809  - Refresh control  RFSH = 1 ; Refresh enabled  - Refresh control  RMODE = 0 ; Auto refresh  - Bank active mode  BACTV = 0 ;Auto precharge mode  - Number of area3 row address bits  A3ROW[1:0] = 01 ;12 bits  - Number of area3 column address bits  A3COL[1:0] = 01 ;9 bits</p> <p><b>Refresh Timer Control/Status Register(RTCSR)</b>  Initial value : H'0000 0000  Recommended set value : H'A55A 0010  - Clock select  CKS[2:0] = 010 ;B<math>\phi</math>/16  - Refresh times  RRC[2:0] = 000 ; 1 time</p> <p><b>Refresh Time Constant Register(RTCOR)</b>  Initial value : H'0000 0000  Recommended set value : H'A55A 0027  *The following shows refresh request intervals in cases when clock select is set to B<math>\phi</math>/16.  1 cycle :400nsec(40MHz/16 = 2.5MHz)  Refresh request intervals for the SDRAM : every 15.625<math>\mu</math>sec  15.625<math>\mu</math>sec /400nsec = 39(0x27) cycles / refresh</p>

[illegible]

### Figure2.3.2 Example of SDRAM Single Read/Write Timing



### 2.3.3 Expand of Flash Memory

M3A-HS86 has installed the mounting space to which the flash memory can be expanded externally.

The mountable flash memory is 32M bit or 64M bit flash memory with 3.3V power-supply voltage, 16-bit bus width, and TSOP-48 pin (20 x 12mm).

By a DIP switch (SW4-4), the validity or invalidity of write protect for flash memory can be switched.

Figure2.3.3 shows an example of 32-Mbit Flash Memory connection.




Figure2.3.3 Connection Example with Flash Memory

Note: Only the M3A-HS86 (3.3V version) can connect the flash memory to outside.

## 2.4 Serial Port Interface

The SH7086 included in the M3A-HS86 contains a UART module. In the M3A-HS86, SCI channel 1 is connected to Serial Port connector J3.

Figure2.4.1 shows the block diagram of serial port interface in the M3A-HS86.




Figure2.4.1 Block Diagram of Serial Port Interface

## 2.5 I/O Ports

In the M3A-HS86, all of the SH7086's I/O ports are connected to the extension bus connector. Some I/O ports are connected to DIP switches and LEDs of the M3A-HS86 board. Users are free to use these ports.

Figure2.5.1 shows the Block Diagram of DIP Switch and LEDs in the M3A-HS86.

Table2.5.1 to Table 2.5.3 list a function of the SH7086 I/O ports in the M3A-HS86.




Figure2.5.1 Block Diagram of DIP Switch and LEDs in M3A-HS86

Table2.5.1 Functions of SH7086 I/O Ports

SH7086		Connection Destinations on M3A-HS86										
Pin No.	Pin Name	Extension Connector										Other Connections
		J6	J7	J8	J9	J10	J11	J12	J13	J14		
1	PE12/TIOC4A/TXD3/SCS/TCK							●			H-UDI connector (J1,J2)	
2	PE13/TIOC4B/MRES/ASEBRKAK/ASEBRK							●			H-UDI connector (J1,J2) MRES SW (Not mounted)	
3	PA23/WRHH/ICIOWR/AH/DQMUU/TIC5W	●					●					
4	PE14/WRHH/ICIOWR/AH /DQMUU/DACK0/TIOC4C							●			LED5	
5	PA22/WRHL/ICIORD/DQMUL/TIC5V	●					●					
6	PA21/CS5/CE1A/CASU/TIC5U	●				●						
7	PE15/CKE/DACK1/TIOC4D/IRQOUT							●				
9	PE16/CS8/TIOC3BS	●					●				User Port (LED6)	
10	PE17/TIOC3DS	●									User Port (LED7)	
12	PE18/TIOC4AS	●									User Port (LED8)	
13	PE19/TIOC4BS	●										
14	PE20/TIOC4CS	●										
15	PE21/TIOC4DS	●										
16	PC0/A0					●						
17	PC1/A1					●					Flash, SDRAM *1	
18	PC2/A2					●					Flash, SDRAM *1	
19	PC3/A3					●					Flash, SDRAM *1	
20	PC4/A4					●					Flash, SDRAM *1	
22	PC5/A5					●					Flash, SDRAM *1	
24	PC6/A6					●					Flash, SDRAM *1	
25	PC7/A7					●					Flash, SDRAM *1	
26	PC8/A8					●					Flash, SDRAM *1	
27	PC9/A9					●					Flash, SDRAM *1	
28	PC10/A10					●					Flash, SDRAM *1	
29	PC11/A11					●					Flash, SDRAM *1	
30	PC12/A12					●					Flash, SDRAM *1	
31	PC13/A13					●					Flash, SDRAM *1	
32	PC14/A14					●					Flash, SDRAM *1	
33	PC15/A15					●					Flash *1	
34	PB0/A16/TIC5WS					●					Flash *1	
36	PB1/A17/TIC5W					●					Flash *1	
38	PA20/CS4/RASU					●						
39	PA19/BACK/TEND1						●					
40	PB2/IRQ0/POE0/SCL						●					
41	PB3/IRQ1/POE1/SDA						●					
42	PA18/BREQ/TEND0						●					
43	PB4/RASL/IRQ2/POE2						●				SDRAM *1	
45	PB5/CASL/IRQ3/POE3						●				SDRAM *1	
46	PB6/A18/BACK/IRQ4/RXD0	●									User Port (Dip SW)	
47	PB7/A19/BREQ/IRQ5/TXD0	●									User Port (Dip SW)	
49	PB8/A20/WAIT/IRQ6/SCK0	●									User Port (Dip SW)	
50	PB9/A21/IRQ7/ADTRG/POE8	●									User Port (Dip SW)	
52	PA14/RD								●		Flash *1	
54	PC18/A18					●					Flash *1	

Note \*1: Only for 3.3V version

Table 2.5.2 Functions of SH7086 I/O Ports

SH7086		Connection destinations on M3A-HS86										
Pin No.	Pin Name	Extension Connector										Other Connections
		J6	J7	J8	J9	J10	J11	J12	J13	J14		
55	PC19/A19					●					Flash *1	
56	PC20/A20					●					Flash *1	
58	PC21/A21					●					Flash *1	
59	PC22/A22					●						
60	PC23/A23					●						
61	PC24/A24					●						
62	PC25/A25					●						
63	PA26/A26/IRQ0	●			●							
65	PA27/A27/IRQ1	●			●							
67	PA28/A28/IRQ2	●			●							
68	PA29/A29/IRQ3	●			●							
69	PD31/D31/TIOC3AS/ADTRG								●			
70	PD30/D30/TIOC3CS/IRQOUT								●			
72	PA13/WRH/DQMLU/WE/POE7						●				SDRAM *1	
73	PA12/WRL/DQMLL/POE6						●				Flash, SDRAM *1	
75	PA11/CS1/POE5					●						
76	PA10/CS0/POE4					●					Flash *1	
77	PA9/FRAME/CKE/IRQ3/TCLKD						●				SDRAM *1	
78	PA8/RDWR/IRQ2/TCLKC						●				SDRAM *1	
79	PA7/CS3/TCLKB						●				SDRAM *1	
80	PA6/CS2/TCLKA				●	●						
81	PD29/D29/CS3/TIOC3BS								●			
82	PD28/D28/CS2/TIOC3DS								●			
83	PD27/D27/DACK1/TIOC4AS								●			
84	PD26/D26/DACK0/TIOC4BS								●			
85	PD25/D25/DREQ1/TIOC4CS								●			
87	PD24/D24/DREQ0/TIOC4DS								●			
88	PD23/D23/IRQ7/AUDSYNC								●			
89	PD22/D22/IRQ6/TIC5US/AUDCK		●						●			
90	PD21/D21/IRQ5/TIC5VS/AUDMD		●						●			
91	PD20/D20/IRQ4/TIC5WS/AUDRST		●						●			
92	PD19/D19/IRQ3/POE7/AUDATA3								●			
93	PD18/D18/IRQ2/POE6/AUDATA2								●			
95	PD17/D17/IRQ1/POE5/AUDATA1								●			
97	PD16/D16/IRQ0/POE4/AUDATA0								●			
98	PD15/D15/TIOC4DS								●		Flash, SDRAM *1	
99	PD14/D14/TIOC4CS								●		Flash, SDRAM *1	
100	PD13/D13/TIOC4BS								●		Flash, SDRAM *1	
101	PD12/D12/TIOC4AS								●		Flash, SDRAM *1	
103	PD11/D11/TIOC3DS								●		Flash, SDRAM *1	
105	PD10/D10/TIOC3CS								●		Flash, SDRAM *1	
106	PD9/D9/TIOC3BS								●		Flash, SDRAM *1	
107	PD8/D8/TIOC3AS								●		Flash, SDRAM *1	
108	PD7/D7/TIC5WS								●		Flash, SDRAM *1	
110	PD6/D6/TIC5VS								●		Flash, SDRAM *1	
111	PD5/D5/TIC5US								●		Flash, SDRAM *1	

Note \*1: Only for 3.3V version

Table 2.5.3 Functions of SH7086 I/O Ports

SH7086		Connection Destinations on M3A-HS86									
Pin No.	Pin Name	Extension Connector									
		J6	J7	J8	J9	J10	J11	J12	J13	J14	Other Connections
112	PD4/D4/TIC5W								●		Flash, SDRAM *1
113	PD3/D3/TIC5V								●		Flash, SDRAM *1
114	PD2/D2/TIC5U								●		Flash, SDRAM *1
115	PD1/D1								●		Flash, SDRAM *1
116	PD0/D0								●		Flash, SDRAM *1
124	PA16/WRHH/ICLOWR/AH/DQMUU /CKE/DREQ2/AUDSYNC							●			H-UDI connector (J1)
125	PA17/WAIT/DACK2								●		
126	PA24/CE2A/DREQ3						●				
127	PA25/CE2B/DACK3/POE8						●				
131	PA15/CK					●		●			SDRAM *1
133	PE0/DREQ0/TIOC0A/AUDCK							●			H-UDI connector (J1)
134	PE1/TEND0/TIOC0B/AUDMD								●		LED2
135	PE2/DREQ1/TIOC0C/AUDRST								●		LED3
137	PE3/TEND1/TIOC0D/AUDATA3							*2			H-UDI connector (J1)
138	PE4/IOIS16/TIOC1A/RXD3/AUDATA2							*2			H-UDI connector (J1)
139	PE5/CS6/CE1B/TIOC1B/TXD3/AUDATA1							*2			H-UDI connector (J1)
140	PE6/CS7/TIOC2A/SCK3/AUDATA0							*2			H-UDI connector (J1)
143	PF0/AN0			●							
144	PF1/AN1	●									
145	PF8/AN8	●									
146	PF9/AN9	●									
147	PF2/AN2	●									
148	PF3/AN3	●									
149	PF10/AN10				●						
150	PF11/AN11				●						
152	PF4/AN4	●									
153	PF5/AN5			●							
154	PF12/AN12				●						
155	PF13/AN13				●						
157	PF6/AN6			●							
158	PF7/AN7	●									
159	PF14/AN14				●						
160	PF15/AN15				●						
164	PA0/CS4/RXD0				●						
165	PA1/CS5/CE1A/TXD0				●						
166	PA2/A25/DREQ0/IRQ0/SCK0				●						
167	PA3/A24/RXD1								●		Serial port (J3)
169	PA4/A23/TXD1								●		Serial port (J3)
170	PA5/A22/DREQ1/IRQ1/SCK1				●						IRQ1 SW
171	PE7/BS/TIOC2B/UBCTRG/RXD2/SSI						●	●			LED4
172	PE8/TIOC3A/SCK2/SSCK/TMS						●				H-UDI connector (J1,J2)
174	PE9/TIOC3B/SCK3/RTS3/TRST							●			H-UDI connector (J1,J2)
175	PE10/TIOC3C/TXD2/SSO/TDI						●				H-UDI connector (J1,J2)
176	PE11/TIOC3D/RXD3/CTS3/TDO							●			H-UDI connector (J1,J2)

Note \*1: Only for 3.3V version

\*2: Connected only when the 0Ω resistance is mounted. It is not mounted initially.

## 2.6 Power Supply Circuit

The M3A-HS86 accepts a 5V power supply as its input and generates 3.3V from it by using a regulator.

The M3A-HS86 (3.3V version) and M3A-HS86 (5V version) are different according to whether R37 and R38 are mounted.

- M3A-HS86 (3.3V version) : R37 is not mounted, R38 is mounted

- M3A-HS86 (5V version) : R37 is mounted, R38 is not mounted

Figure2.6.1 shows the block diagram of power supply circuit in the M3A-HS86.




Figure2.6.1 Block Diagram of Power Supply Circuit

## 2.7 Clock Module

The clock module in the M3A-HS86 consists of the following two blocks:

- Output from an oscillator connected to EXTAL of the SH7086
- Ceramic resonator connected to EXTAL and XTAL

The M3A-HS86 has a 10MHz oscillator connected to it as standard specification.

The system clock output (PA15/CK) of SH7086 is connected to an extension connector through the damping resistor. To connect an extension board to an extension connector, we recommend including a clock buffer that contains a PLL to ensure that the board will be supplied with a stable clock signal.

Figure2.7.1 shows the block diagram of clock module.




Figure2.7.1 Block Diagram of Clock Module



## 2.8 Reset Module

Reset module controls the reset signal connected to the SH7086, which is mounted on the M3A-HS86. Moreover, when the flash memory is mounted, it is used as a reset signal of the flash memory.

Figure2.8.1 shows the block diagram of reset module in the M3A-HS86.




Figure2.8.1 Block Diagram of Reset Module

## 2.9 Interrupt Switches

In the M3A-HS86, the switch is connected with the PA5/IRQ1 pin and NMI pin of the SH7086. LED to confirm that the switch has been pushed is connected. In addition, MRES switch can be mounted on PE13/ $\overline{\text{MRES}}$  pin. However, it cannot be mounted when E10A-USB is used because  $\overline{\text{MRES}}$  pin is multiplexed with the signal  $\overline{\text{ASEBRKAK/ASEBRK}}$ .

Figure2.9.1 shows the interrupt block diagram in the M3A-HS86.




Figure2.9.1 Interrupt Block Diagram

## 2.10 E10A-USB Interface

The M3A-HS86 has a 36-pin H-UDI connector and 14-pin H-UDI connector included in it for connection to the E10A-USB.

Because the SH7086's H-UDI pins and AUD pins are being output to the extension connector, do not use the applicable pins of the extension connector when debugging with the H-UDI connector.

Figure2.10.1 shows the block diagram of E10A-USB interface.




Figure2.10.1 Block Diagram of E10A-USB Interface

Note: 36-pin type and 14 pin type of the H-UDI connector cannot be used at the same time.

This is a blank page

## Chapter 3

---

### Operational Specifications

## 3.1 M3A-HS86 Connectors Outline

Figure3.1.1 shows M3A-HS86 connector assignments.




Figure3.1.1 M3A-HS86 Connector Assignments

## 3.1.1 H-UDI Connector (J1,J2)

M3A-HS86 has the 36-pin H-UDI (J1) connector and 14-pin H-UDI (J2) connector included in it for connection to the E10A-USB emulator.

Figure3.1.2 shows a pin assignment of H-UDI (J1) connector.




Figure3.1.2 Pin Assignment of H-UDI (J1) Connector

Table3.1.1 lists pin assignments of H-UDI connector.

Table3.1.1 Pin Assignments of H-UDI (J1) Connector

Pin	Signal Name	Pin	Signal Name
1	AUDCK	19	TMS
2	GND	20	GND
3	AUDATA0	21	TRST
4	GND	22	(GND)
5	AUDATA1	23	TDI
6	GND	24	GND
7	AUDATA2	25	TDO
8	GND	26	GND
9	AUDATA3	27	ASEBRKAK/ASEBRK
10	GND	28	GND
11	$\overline{\text{AUDSYNC}}$	29	UVCC
12	GND	30	GND
13	NC	31	$\overline{\text{RES}}$
14	GND	32	GND
15	NC	33	GND
16	GND	34	GND
17	TCK	35	NC
18	GND	36	GND

Figure3.1.3 shows a pin assignment of H-UDI (J2) connector.




Figure3.1.3 Pin Assignment of H-UDI (J2) Connector

Table3.1.2 lists pin assignments of H-UDI (J2) connector.

Table3.1.2 Pin Assignments of H-UDI (J2) Connector

Pin	Signal Name	Pin	Signal Name
1	TCK	8	NC
2	TRST	9	(GND)
3	TDO	10	GND
4	ASEBRKAK/ASEBRK	11	UVCC
5	TMS	12	GND
6	TDI	13	GND
7	RES	14	GND



### 3.1.2 Serial Port Connector (J3)

The M3A-HS86 includes a serial port connector (J3) for serial communication.

Figure3.1.4 shows a pin assignment of serial port connector.




Figure3.1.4 Pin Assignment of Serial Port Connector (J3)

Table3.1.3 lists pin assignments of serial port connector.

Table3.1.3 Pin Assignments of Serial Port Connector (J3)

Pin	Signal Name	Pin	Signal Name
1	NC	6	DSR
2	RXD	7	RTS
3	TXD	8	CTS
4	DTR	9	NC
5	GND		

Pins 4-6 are loop back-connected. Pins 7-8 are loop back-connected.

### 3.1.3 External Power Supply Connectors for the SH7086 (J4)

The M3A-HS86 includes the external power supply connector pin for the SH7086.

Figure3.1.5 shows a pin assignment of power supply connector.




Figure3.1.5 Pin Assignment of Power Supply Connector (J4)

Table3.1.4 lists a pin assignment of power supply connector for the SH7086.

Table3.1.4 Pin Assignment of Power Supply Connector (J4)

Pin	Signal Name	Pin	Signal Name
1	+3.3V or +5.0V	2	GND

### 3.1.4 Power Supply Connector (J5)

The M3A-HS86 includes a power supply connector for the board itself.

Figure3.1.6 shows a pin assignment of power supply connector.




Figure3.1.6 Pin Assignment of Power Supply Connector (J5)

Table3.1.5 lists a pin assignment of power supply connector for the M3A-HS86.

Table3.1.5 Pin Assignment of Power Supply Connector (J5)

Pin	Signal Name	Pin	Signal Name
1	+5V	2	GND

## 3.1.5 User I/O Connector (J6-J8)

The M3A-HS86 includes user I/O connectors to which the internal peripheral function pins of the SH7086 applicable for motor control (e.g., MTU2 and AD functions) are connected. Figure3.1.7 shows a pin assignment of each user I/O connector. Table3.1.6 lists pin assignments of user I/O connectors (J6).




Figure3.1.7 Pin Assignment of User I/O Connectors (J6-J8)

Table3.1.6 Pin Assignments of User I/O Connector (J6)

Pin	Signal Name	Other Connection
1	+5V	-
2	GND	-
3	PF8/AN8	-
4	PA21/CS5/CE1A/CASU/TIC5U	Extension connector (J10)
5	PA22/WRHL/ICIORD/DQMUL/TIC5V	Extension connector (J11)
6	PA23/WRHH/ICIOWR/AH/DQMUU/TIC5W	Extension connector (J11)
7	PE16/CS8/TIOC3BS	Extension connector (J11), LED6
8	PE18/TIOC4AS	LED8
9	PE19/TIOC4BS	-
10	PE17/TIOC3DS	LED7
11	PE20/TIOC4CS	-
12	PE21/TIOC4DS	-
13	PA26/A26/IRQ0	Extension connector (J9)
14	PA27/A27/IRQ1	Extension connector (J9)
15	PA28/A28/IRQ2	Extension connector (J9)
16	PA29/A29/IRQ3	Extension connector (J9)
17	PF2/AN2	-
18	PF3/AN3	-
19	PF4/AN4	-
20	PF9/AN9	-
21	PB6/A18/BACK/IRQ4/RXD0	DIP switch (SW3)
22	PB7/A19/BREQ/IRQ5/TXD0	DIP switch (SW3)
23	PB8/A20/WAIT/IRQ6/SCK0	DIP switch (SW3)
24	PB9/A21/IRQ7/ADTRG/POE8	DIP switch (SW3)
25	PF1/AN1	-
26	PF7/AN7	-

Table3.1.7 lists pin assignments of user I/O connector (J7).

Table3.1.7 Pin Assignments of User I/O Connector (J7)

Pin	Signal Name	Other Connection
1	PD20/D20/IRQ4/TIC5WS	Extension connector (J13)
2	PD21/D21/IRQ5/TIC5VS	Extension connector (J13)
3	PD22/D22/IRQ6/TIC5US	Extension connector (J13)

Table3.1.8 lists pin assignments of user I/O connector (J8).

Table3.1.8 Pin Assignments of User I/O Connector (J8)

Pin	Signal Name	Other Connection
1	PF0/AN0	-
2	PF6/AN6	-
3	PF5/AN5	-

## 3.1.6 Extension Connectors (J9-J13)

The M3A-HS86 includes extension connectors to which the I/O pins of the SH7086 are connected.

MIL standard connectors can be connected to J9-J13, allowing the user to create extension board or monitor the SH7086 bus signals.

Figure3.1.8 shows a pin assignment of extension connector.




Figure3.1.8 Pin Assignment of Extension Connectors (J9-J13)

Table3.1.9 lists pin assignments of extension connector (J9).

Table3.1.9 Pin Assignments of Extension Connectors (J9)

Pin	Signal Name	Other Connection
1	NC	-
2	NC	-
3	NC	-
4	NC	-
5	PA0/RXD0/CS4	-
6	PA1/TXD0/CS5/CE1A	-
7	PA2/A25/DREQ0/IRQ0/SCK0	-
8	PA5/A22/DREQ1/IRQ1/SCK1	IRQ switch (SW6)
9	PA6/CS2/TCLKA	Extension connector (J10)
10	PA26/A26/IRQ0	User I/O connector (J6)
11	PA27/A27/IRQ1	User I/O connector (J6)
12	PA28/A28/IRQ2	User I/O connector (J6)
13	PA29/A29/IRQ3	User I/O connector (J6)
14	PF10/AN10	-
15	PF11/AN11	-
16	PF12/AN12	-
17	PF13/AN13	-
18	PF14/AN14	-
19	PF15/AN15	-
20	GND	-

Table3.1.10 lists pin assignments of extension connectors.

Table3.1.10 Pin Assignments of Extension Connectors (J10)

Pin	Signal Name	Other Connection
1	3.3V	-
2	3.3V	-
3	WDTOVF	-
4	PC25/A25	-
5	PC24/A24	-
6	PC23/A23	-
7	PC22/A22	-
8	PC21/A21	Flash memory <sup>*2</sup>
9	PC20/A20	Flash memory <sup>*2</sup>
10	PC19/A19	Flash memory <sup>*2</sup>
11	PC18/A18	Flash memory <sup>*2</sup>
12	PB1/A17	Flash memory <sup>*2</sup>
13	PB0/A16	Flash memory <sup>*2</sup>
14	PC15/A15	Flash memory <sup>*2</sup>
15	PC14/A14	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
16	PC13/A13	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
17	PC12/A12	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
18	PC11/A11	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
19	PC10/A10	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
20	GND	-
21	NC	-
22	NC	-
23	PA15/CK (EXCLK)	Extension connector (J12), SDRAM <sup>*1</sup> , Clock buffer <sup>*2</sup>
24	PC9/A9	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
25	PC8/A8	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
26	PC7/A7	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
27	PC6/A6	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
28	PC5/A5	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
29	PC4/A4	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
30	PC3/A3	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
31	PC2/A2	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
32	PC1/A1	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
33	PC0/A0	-
34	PA10/CS0/POE4	Flash memory <sup>*2</sup>
35	PA11/CS1/POE5	-
36	PA6/CS2/TCLKA	Extension connector (J9)
37	PA20/CS4/RASU	-
38	PA21/CS5/CASU/CE1A/TIC5U	User I/O connector (J6)
39	RES	Reset module, Flash memory <sup>*2</sup>
40	GND	-

Notes \*1: M3A-HS86 (3.3V version) only.

\*2: Not mounted.



Table3.1.11 lists pin assignments of extension connectors.

Table3.1.11 Pin Assignments of Extension Connectors (J11)

Pin	Signal Name	Other Connection
1	PB2/IRQ0/POE0/SCL	-
2	PB3/IRQ1/POE1/SDA	-
3	PA7/ $\overline{\text{CS3}}$ /TCLKB	SDRAM <sup>*1</sup>
4	PA8/RDWR/IRQ2/TCLKC	SDRAM <sup>*1</sup>
5	PA12/WRL/DQMLL/POE $\overline{6}$	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
6	PA13/WRH/DQMLU/ $\overline{\text{WE}}$ /POE $\overline{7}$	SDRAM <sup>*1</sup>
7	PA22/WRHL/ICIORD/DQMUL/TIC5V	User I/O connector (J6)
8	PA23/WRHH/ICIOWR/AH/DQMUU/TIC5W	User I/O connector (J6)
9	PA9/FRAME/CKE/IRQ3/TCLKD	SDRAM <sup>*1</sup>
10	PB4/RASL/IRQ2/POE2	SDRAM <sup>*1</sup>
11	PB5/ $\overline{\text{CASL}}$ /IRQ3/POE $\overline{3}$	SDRAM <sup>*1</sup>
12	PE16/ $\overline{\text{CS8}}$ /TIOC3BS	User I/O connector (J6), LED6
13	PE8/SCK2/TIOC3A/SSCK/TMS	H-UDI connector (J1,J2)
14	PE10/TXD2/TIOC3C/SSO/TDI	H-UDI connector (J1,J2)
15	PE7/RXD2/BS/TIOC2B/UBCTRG/SSI	Extension connector (J12), LED4
16	PA24/CE2A/DREQ3	-
17	PA25/CE2B/DACK3/POE $\overline{8}$	-
18	PA18/BREQ/TEND0	-
19	PA19/BACK/TEND1	-
20	GND	-

Notes \*1: M3A-HS86 (3.3V version) only.

\*2: Not mounted.

Table3.1.12 lists pin assignments of extension connectors.

Table3.1.12 Pin Assignments of Extension Connectors (J12)

Pin	Signal Name	Other Connection
1	NC	-
2	NC	-
3	NC	-
4	NC	-
5	NC	-
6	PE0/DREQ0/TIOC0A/AUDCK	H-UDI connector (J1)
7	NC (PE3/TEND1/TIOC0D/AUDATA3 when R68 mounted)	H-UDI connector (J1)
8	NC (PE4/IOIS16/TIOC1A/RXD3/AUDATA2 when R69 mounted)	H-UDI connector (J1)
9	NC (PE5/CS6/CE1B/TIOC1B/TXD3/AUDATA1(when R70 mounted)	H-UDI connector (J1)
10	NC (PE6/CS7/TIOC2A/SCK3/AUDATA0 when R71 mounted)	H-UDI connector (J1)
11	PE7/RXD2/BS/TIOC2B/UBCTR $\overline{\text{G}}$ /SSI	Extension connector (J11), LED4
12	PE9/TIOC3B/SCK3/RTS3/TRST	H-UDI connector (J1,J2)
13	PE11/TIOC3D/RXD3/CTS3/TDO	H-UDI connector (J1,J2)
14	PE12/TIOC4A/TXD3/SCS/TCK	H-UDI connector (J1,J2)
15	PE13/TIOC4B/MRES/ASEBRKAK/ASEBRK	H-UDI connector (J1,J2), MRES switch <sup>*2</sup>
16	PE14/WRHH/ICIOR $\overline{\text{W}}$ /AH/DQM $\overline{\text{U}}$ /DACK0/TIOC4C	LED5
17	PE15/CKE/DACK1/TIOC4D/IRQOUT	-
18	PA15/CK	Extension connector (J12), SDRAM <sup>*1</sup> , Clock buffer <sup>*2</sup>
19	PA16/WRHH/ICIOR $\overline{\text{W}}$ /AH/DQM $\overline{\text{U}}$ /CKE/DREQ2/AUDSYN $\overline{\text{C}}$	H-UDI connector (J1)
20	GND	-

Notes \*1: M3A-HS86 (3.3V version) only.

\*2: Not mounted.

Table3.1.13 lists pin assignments of the extension connectors.

Table3.1.13 Pin Assignments of the Extension Connectors (J13)

Pin	Signal Name	Other Connection
1	5V	-
2	5V	-
3	PA17/WAIT/DACK2	-
4	PD31/D31/TIOC3AS/ADTRG	-
5	PD30/D30/TIOC3CS/IRQOUT	-
6	PD29/D29/CS3/TIOC3BS	-
7	PD28/D28/CS2/TIOC3DS	-
8	PD27/D27/DACK1/TIOC4AS	-
9	PD26/D26/DACK0/TIOC4BS	-
10	PD25/D25/DREQ1/TIOC4CS	-
11	PD24/D24/DREQ0/TIOC4DS	-
12	PD23/D23/IRQ7/AUDSYNC	-
13	PD22/D22/IRQ6/TIC5US/AUDCK	Extension connector (J7)
14	PD21/D21/IRQ5/TIC5VS	Extension connector (J7)
15	PD20/D20/IRQ4/TIC5WS	Extension connector (J7)
16	PD19/D19/IRQ3/POE7/AUDATA3	-
17	PD18/D18/IRQ2/POE6/AUDATA2	-
18	PD17/D17/IRQ1/POE5/AUDATA1	-
19	PD16/D16/IRQ0/POE4/AUDATA0	-
20	GND	-
21	PE2/DREQ1/TIOC0C	LED3
22	PE1/TEND0/TIOC0B	LED2
23	PA14/RD	Flash memory <sup>*2</sup>
24	PD15/D15/TIOC4DS	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
25	PD14/D14/TIOC4CS	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
26	PD13/D13/TIOC4BS	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
27	PD12/D12/TIOC4AS	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
28	PD11/D11/TIOC3DS	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
29	PD10/D10/TIOC3CS	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
30	PD9/D9/TIOC3BS	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
31	PD8/D8/TIOC3AS	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
32	PD7/D7/TIC5WS	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
33	PD6/D6/TIC5VS	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
34	PD5/D5/TIC5US	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
35	PD4/D4/TIC5W	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
36	PD3/D3/TIC5V	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
37	PD2/D2/TIC5U	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
38	PD1/D1	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
39	PD0/D0	SDRAM <sup>*1</sup> , Flash memory <sup>*2</sup>
40	GND	-

Notes \*1: M3A-HS86 (3.3V Version) only.

\*2: Not mounted.

## 3.1.7 Extension Connector (J14)

Extension connector(J14) connects the pins necessary for writing a on-chip flash memory of SH7086.

Figure 3.1.9 lists pin assignments of the extension connectors.




Figure 3.1.9 Pin Assignments of the Extension Connector (J14)

Table 3.1.14 lists pin assignments of the extension connector (J14).

Table 3.1.14 Pin Assignments of the Extension Connector (J14)

Pin	Signal Name	Other Connection
1	RES	-
2	GND	-
3	FWE	FWE pin select jumper (JP2)
4	GND	-
5	MD0	DIP switch for system setting (SW4-3)
6	GND	-
7	MD1	DIP switch for system setting (SW4-2)
8	GND	-
9	NC	-
10	GND	-
11	NC	-
12	GND	-
13	NC	-
14	GND	-
15	PA4/A23/TXD1	Serial port connector (J3)
16	GND	-
17	PA3/A24/RXD1	Serial port connector (J3)*
18	VCC	-
19	NC	-
20	VCC	-

Note \*: It is connected to the output pin of RS-232C driver.

## 3.2 Outline of Switches and LEDs

The M3A-HS86 includes switches and LEDs as its operational components.

Figure3.2.1 shows the M3A-HS86 operational component assignment.




Figure3.2.1 M3A-H86 Operational Component Assignment

### 3.2.1 SH7086 Power Supply Select Jumpers (JP1)

The JP1 allow the sources for the SH7086 power supply voltages to be selected.

Figure3.2.2 shows the SH7086 power supply voltage select jumper assignment (JP1). Table3.2.1 lists the jumper setting for selecting SH7086 Power Supply Voltage (JP1).




Figure3.2.2 SH7086 Power Supply Voltage Select Jumpers Assignment (JP1)

Table3.2.1 Jumper Setting for Selecting SH7086 Power Supply Voltage (JP1)

Jumper	Setting	Function
JP1	1 - 2	5V fixed power supply voltage (supplied from J5)
PWRSEL	2 - 3	External power supply voltage (supplied from J4)

■ : Initial Setting

Note: Do not change jumper settings during the operation of M3A-HS86. Ensure to turn off the power for the M3A-HS86 before changing jumper settings.

### 3.2.2 FWE Pin Select Jumper (JP2)

The JP2 allows the connection for the FWE pin to be selected.

Figure3.2.3 shows FWE pin select jumper (JP2) assignment. Table3.2.2 lists jumper setting for selecting FWE pin (JP2).




Figure3.2.3 FWE Pin Select Jumper (JP2) Assignment

Table3.2.2 Jumper Setting FWE Pin (JP2)

Jumper	Setting	Function
JP2	1 - 2	The FWE pin of SH7086 is connected with SW4-1.
FDMSEL	2 - 3	The FWE pin of SH7086 is connected with J14 connector.

■ : Initial Setting

**Note:** Do not change jumper settings during the operation of M3A-HS86. Ensure to turn off the power for the M3A-HS86 before changing jumper settings.

### 3.2.3 Switch and LED Functions

The M3A-HS86 includes six switches and nine LEDs. The MRES switch can be mounted as the option. However, MRES pin is multiplexed with  $\overline{\text{ASEBRKAK}}/\overline{\text{ASEBRK}}$  pin, so do not mount the switch MRES when H-UDI connectors (J1, J2) are used. Figure3.2.4 shows the switch and LED pin layout on M3A-HS86 board. Table3.2.3 lists switches mounted on M3A-HS86.




Figure3.2.4 Switch and LED Pin Assignment on M3A-HS86 Board

Table3.2.3 Switches Mounted on M3A-HS86

No.	Function	Remarks
SW1	System power on/off switch	-
SW2	System reset input switch	See section 2.8 for details.
SW3	DIP switch open to the user (4-pole) SW3-1 OFF : PB6=H, ON : PB6=L SW3-2 OFF : PB7=H, ON : PB7=L SW3-3 OFF : PB8=H, ON : PB8=L SW3-4 OFF : PB9=H, ON : PB9=L	PB6, PB7, PB8 and PB9 are pulled up. See section 2.5 on chapter 2 for details.
SW4	System setup DIP switch (4-pole)	See Table3.2.4 for the functions
SW5	NMI input switch	See section 2.9 of chapter 2 for details.
SW6	IRQ1 input switch	See section 2.9 of chapter 2 for details.
SW7	MRES* input switch	Not mounted.

\*: By MRES (manual reset), each register of the on-chip peripheral module is not initialized though an internal state of CPU is initialized.



Table3.2.4 lists functions of switch SW4. SH7086 operating mode is determined by the combination of the MD0, MD1 and FWE pins. Table3.2.5 lists the selection of SH7086 operating modes.

Table3.2.4 Functions of Switch SW4

No.	Setting	Function	
SW4-1 FWE	OFF	FWE=H (Releasing the writing/erasing protects of on-chip flash memory)	MCU operating mode setting (See.Table3.2.5)
	ON	FWE=L (Setting the writing erasing protects of on-chip flash memory)	
SW4-2 MD1	OFF	MD1 pin state "H"	
	ON	MD1 pin state "L"	
SW4-3 MD0	OFF	MD0 pin state "H"	
	ON	MD0 pin state "L"	
SW4-4 FLASH Lock	OFF	Releasing the write protect in the on-chip flash memory (WP#pin is "H")	
	ON	Setting the write protect in the on-chip flash memory (WP#pin is "L")	

Initial Setting

Table3.2.5 Selection of SH7086 Operating Mode

SW4-1 (FWE)	SW4-2 (MD1)	SW4-3 (MD0)	SH7086 Operating Mode	
			Operating Mode	Mode Name
ON	ON	ON	Mode0	MCU extension mode0 (On-chip ROM not active, CS0 space:16bit bus)
ON	ON	OFF	Mode1	MCU extension mode1 (On-chip ROM not active, CS0 space:32bit bus))
ON	OFF	ON	Mode2	MCU extension mode2 (On-chip ROM active)
ON	OFF	OFF	Mode3	Single chip mode (On-chip ROM active)
OFF	ON	ON	Mode4	Boot mode (On-chip ROM active)
OFF	ON	OFF	Mode5	User boot mode (On-chip ROM active)
OFF	OFF	ON	Mode6	User programming mode (On-chip ROM active)
OFF	OFF	OFF	Mode7	User programming mode (On-chip ROM active)

Initial Setting

Table3.2.6 lists functions of LEDs mounted in M3A-HS86.

Table3.2.6 Functions of LEDs mounted in M3A-HS86

No.	Color	Functions/Remarks
LED1	Blue	Power-on LED (LED1 lights when power is supplied)
LED2	Green	Open to user (LED2 lights when PE1 outputs "L")
LED3	Green	Open to user (LED3 lights when PE2 outputs "L")
LED4	Green	Open to user (LED4 lights when PE7 outputs "L")
LED5	Green	Open to user (LED5 lights when PE14 outputs "L")
LED6	Green	Open to user (LED6 lights when PE16 outputs "L")
LED7	Green	Open to user (LED7 lights when PE17 outputs "L")
LED8	Green	Open to user (LED8 lights when PE18 outputs "L")
LED9	Red	Interrupt confirmation (LED9 lights red when pushing NMI switch (SW5)).
	Yellow green	Interrupt confirmation (LED9 lights yellow green when pushing IRQ1 switch (SW6)).

## 3.3 Board Dimensions of M3A-HS86

Figure3.3.1 shows board dimensions of M3A-HS86.




Figure3.3.1 Board Dimensions of M3A-HS86

---

Appendix  
M3A-HS86 SCHEMATICS

This is a blank page

SH7086 CPU BOARD M3A-HS86 SCHEMATICS

TITLE	PAGE
INDEX	1
CPU SH7086	2
FLASH	3
SDRAM	4
UDI/RESET/UART/POWER	5
BUS CONNECTORS/PUSH SW	6
OTHERS	7

Note:



5VCC = 5V  
3VCC = 3.3V  
VCC = 3.3V(M3A-HS86G50,M3A-HS86G51)  
5V(M3A-HS86G55,M3A-HS86G56)

R = Fixed Resistors  
RA = Resistor Array  
C = Ceramic Caps  
CE = Tantalum Electrolytic Caps  
CP = Decoupling Caps

[Note]   :not mounted

CHANGE	Ver. 1.0			RENESAS SOLUTIONS CORPORATION				M3A-HS86 INDEX ( 1 / 7 )
		SCALE		DRAWN	CHECKED	DESIGNED	APPROVED	
		DATE	07-01-18					DK30504

FWE	MD1	MD0	Mode
"0"	"0"	"0"	MCU extension mode 0
		"1"	MCU extension mode 1
	"1"	"0"	MCU extension mode 2
"1"	"0"	"1"	Single chip mode
		"1"	Boot mode
	"1"	"0"	User Programming mode



[5,6] MD1  
[5,6] MD0

[5] FWE

[4,6] PA15/CK  
[3,5,6] \_RESET

[6] NMI  
[6] PA5/IRQ1

[6] \_WDTOVF

[3,6] PA10/\_CS0  
[6] PA11/\_CS1  
[6] PA6/\_CS2

[4,6] PA7/\_CS3  
[6] PA20/\_CS4/\_RASU  
[6] PA21/\_CS5/\_CASU

[3,6] PA14/\_RD  
[4,6] PB4/\_RASL  
[4,6] PB5/\_CASL

[4,6] PA13/DQMLU/\_WRH  
[3,4,6] PA9/CKE  
[4,6] PA8/RDWR

[6] PA23/\_WRHH  
[6] PA22/\_WRHL  
[6] PA17/\_WAIT

[6] PE15/\_IRQOUT  
[6] PA19/\_BACK  
[6] PA18/\_BREQ

[5,6] PB6/RXD0/IRQ4  
[5,6] PB7/TXD0/IRQ5  
[5,6] PB8/SCK0/IRQ6  
[5,6] PB9/\_ADTRG/IRQ7

[5,6] PE1/TIOC0B  
[5,6] PE2/TIOC0C  
[5,6] PE7/TIOC2B  
[5,6] PE14/\_WRHH  
[6] PE16/TIOC3BS  
[6] PE17/TIOC3DS  
[6] PE18/TIOC4AS

[6] PE19/TIOC4BS  
[6] PE20/TIOC4CS  
[6] PE21/TIOC4DS  
[6] PA24/DREQ3  
[6] PA25/DACK3

[6] AN0  
[6] AN1  
[6] AN2  
[6] AN3  
[6] AN4  
[6] AN5  
[6] AN6  
[6] AN7  
[6] AN8  
[6] AN9  
[6] AN10  
[6] AN11  
[6] AN12  
[6] AN13  
[6] AN14  
[6] AN15

[6] PA0/RXD0/\_CS4  
[6] PA1/TXD0/\_CS5  
[6] PA2/SCK0/IRQ0

[6] PB2/SCL/IRQ0  
[6] PB3/SDA/IRQ1

[5,6] PA3/RXD1  
[5,6] PA4/TXD1

119 MD1  
121 MD0  
123 FWE

118 XTAL  
120 EXTAL

131 PA15/CK  
132C \_RES

122 NMI  
170 IRQ1/PA5/A22/DREQ1/SCK1

53C \_WDTOVF

76 \_CS0/PA10/\_POE4  
75 \_CS1/PA11/\_POE5  
80 \_CS2/PA6/TCLKA  
79 \_CS3/PA7/TCLKB  
38 \_CS4/\_RASU/PA20  
6 \_CS5/\_CE1A/\_CASU/PA21/TIC5U

52 \_RD/PA14  
43 \_RASL/PB4/IRQ2/\_POE2  
45 \_CASL/PB5/IRQ3/\_POE3

72 DQMLU/\_WRH/\_WE/PA13/\_POE7  
77 DQMLL/\_WRL/PA12/\_POE6  
78 RDWR/PA8/IRQ2/TCLKC  
3 \_WRHH/\_ICIORW/\_AH/DQMUI/PA23/TIC5W  
5 \_WRHL/\_ICIOR/DQMUL/PA22/TIC5V  
125 \_WAIT/PA17/DACK2

7 \_IRQOUT/PE15/CKE/DACK1/TIOC4D  
39 \_BACK/PA19/TEND1  
42 \_BREQ/PA18/TEND0

46 PB6/RXD0/A18/\_BACK/IRQ4  
47 PB7/TXD0/A19/\_BREQ/IRQ5  
49 PB8/SCK0/A20/\_WAIT/IRQ6  
50 PB9/\_ADTRG/A21/IRQ7/\_POE8

134 PE1/TEND0/TIOC0B/AUDMD  
135 PE2/DREQ1/TIOC0C/\_AUDRST  
171 PE7/\_BS/TIOC2B/\_UBCTRGR/RXD2/SSI  
4 PE14/\_WRHH/\_ICIORW/\_AH/DQMUI/DACK0/TIOC4C  
9 PE16/\_CS8/TIOC3BS  
10 PE17/TIOC3DS  
12 PE18/TIOC4AS

13 PE19/TIOC4BS  
14 PE20/TIOC4CS  
15 PE21/TIOC4DS  
126 PA24/\_CE2A/DREQ3  
127 PA25/\_CE2B/DACK3/\_POE8

143 AN0/PF0  
144 AN1/PF1  
147 AN2/PF2  
148 AN3/PF3  
152 AN4/PF4  
153 AN5/PF5  
157 AN6/PF6  
158 AN7/PF7  
145 AN8/PF8  
146 AN9/PF9  
149 AN10/PF10  
150 AN11/PF11  
154 AN12/PF12  
155 AN13/PF13  
159 AN14/PF14  
160 AN15/PF15

164 RXD0/PA0/\_CS4  
165 PA1/TXD0/\_CS5  
166 SCK0/PA2/A25/DREQ0/IRQ0

40 SCL/PB2/IRQ0/\_POE0  
41 SDA/PB3/IRQ1/\_POE1

167 RXD1/PA3/A24  
169 TXD1/PA4/A23



A0/PC0  
A1/PC1  
A2/PC2  
A3/PC3  
A4/PC4  
A5/PC5  
A6/PC6  
A7/PC7  
A8/PC8  
A9/PC9  
A10/PC10  
A11/PC11  
A12/PC12  
A13/PC13  
A14/PC14  
A15/PC15  
A16/PB0/TIC5WS  
A17/PB1/TIC5W  
A18/PC18  
A19/PC19  
A20/PC20  
A21/PC21  
A22/PC22  
A23/PC23  
A24/PC24  
A25/PC25  
A26/PA26/IRQ2  
A27/PA27/IRQ1  
A28/PA28/IRQ3  
A29/PA29/IRQ3

D0/PD0  
D1/PD1  
D2/PD2/TIC5U  
D3/PD3/TIC5V  
D4/PD4/TIC5W  
D5/PD5/TIC5US  
D6/PD6/TIC5VS  
D7/PD7/TIC5WS  
D8/PD8/TIOC3AS  
D9/PD9/TIOC3BS  
D10/PD10/TIOC3CS  
D11/PD11/TIOC3DS  
D12/PD12/TIOC4AS  
D13/PD13/TIOC4BS  
D14/PD14/TIOC4CS  
D15/PD15/TIOC4DS

D16/PD16/IRQ0/\_POE4/AUDATA0  
D17/PD17/IRQ1/\_POE5/AUDATA1  
D18/PD18/IRQ2/\_POE6/AUDATA2  
D19/PD19/IRQ3/\_POE7/AUDATA3  
D20/PD20/IRQ4/TIC5WS/\_AUDRST  
D21/PD21/IRQ5/TIC5VS/AUDMD  
D22/PD22/IRQ6/TIC5US/AUDCK  
D23/PD23/IRQ7/\_AUDSYNC  
D24/PD24/DREQ0/TIOC4DS  
D25/PD25/DREQ1/TIOC4CS  
D26/PD26/DACK0/TIOC4BS  
D27/PD27/DACK1/TIOC4AS  
D28/PD28/\_CS2/TIOC3DS  
D29/PD29/\_CS3/TIOC3BS  
D30/PD30/TIOC3CS/\_IRQOUT  
D31/PD31/TIOC3AS/\_ADTRG

116 D0  
115 D1  
114 D2  
113 D3  
112 D4  
111 D5  
110 D6  
108 D7  
107 D8  
106 D9  
105 D10  
103 D11  
101 D12  
100 D13  
99 D14  
98 D15

97 D16  
95 D17  
93 D18  
92 D19  
91 D20  
90 D21  
89 D22  
88 D23  
87 D24  
85 D25  
84 D26  
83 D27  
82 D28  
81 D29  
70 D30  
69 D31

1 PE12/TCK [5,6]  
175 PE8/TMS [5,6]  
176 PE10/TDI [5,6]  
174 PE9/\_TRST [5,6]  
51 \_ASEMD0 [5]  
2 PE13/\_ASEBRKAK/\_ASEBRK [5,6]

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

A0:29] [3,4,6]

D0:31] [3,4,6]

1 PE12/TCK [5,6]  
175 PE8/TMS [5,6]  
176 PE10/TDI [5,6]  
174 PE9/\_TRST [5,6]  
51 \_ASEMD0 [5]  
2 PE13/\_ASEBRKAK/\_ASEBRK [5,6]

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]

130 PLLVSS

142 AVSS  
150 AVSS

37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS

133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137 AUDATA3

1 PE0/AUDCK [5,6]  
PA16/\_AUDSYNC [5,6]  
PE6/AUDATA0 [5,6]  
PE5/AUDATA1 [5,6]  
PE4/AUDATA2 [5,6]  
PE3/AUDATA3 [5,6]


130 PLLVSS

142 AVSS  
150 AVSS


37 VCL  
44 VSS  
71 VCL  
64 VSS  
129 VCL  
117 VSS  
173 VCL  
163 VSS

8 VSS  
23 VSS  
57 VSS  
86 VSS  
96 VSS  
104 VSS  
141 VSS


133 AUDCK  
124 AUDSYNC  
140 AUDATA0  
139 AUDATA1  
138 AUDATA2  
137



CHANGE	Ver. 1.0			RENESAS SOLUTIONS CORPORATION				M3A-HS86	
		SCALE		DRAWN	CHECKED	DESIGNED	APPROVED	FLASH MEMORY ( 3 / 7 )	
		DATE	07-01-18					DK30504	



Decoupling Caps




[Note]  
M3A-HS86G50,M3A-HS86G51(3.3V Version): U4,R14-R22,RA7,RA8,CP19-CP22 mounted  
M3A-HS86G55,M3A-HS86G56(5V Version): U4,R14-R22,RA7,RA8,CP19-CP22 not mounted


CHANGE	Ver. 1.0			RENESAS SOLUTIONS CORPORATION				M3A-HS86
		SCALE		DRAWN	CHECKED	DESIGNED	APPROVED	SDRAM ( 4 / 7 )
		DATE	07-01-18					DK30504



## H-UDI INTERFACE




## Power On Reset




```
td = 34ms[0.34*Cd(pF)usec]
M3A-HS86G50,M3A-HS86G51:Ra=10K,Rb=10K
Vs = 2.5V[1.25*((Ra+Rb)/Rb)]
M3A-HS86G55,M3A-HS86G56:Ra=20K,Rb=10K
Vs = 3.75V[1.25*((Ra+Rb)/Rb)]
```

## User Port




## SERIAL CONNECTOR (COM)



## 5V TO 3.3V LINEAR REGULATOR


```
1-2 Power On
2-3 Power Off
```




$$V_{OUT} = V_{REF} * (1 + R_b/R_a) + I_{ADJ} * (R_b)$$

All regulator TABs are VOUT.


## EXTERNAL POWER



## POWER LED




1-2 Fixed VCC  
2-3 External VCC



M3A-HS86G50,M3A-HS86G51:R38 mounted
M3A-HS86G55,M3A-HS86G56:R37 mounted

Mode  
Switch



1	2	3	Mode
ON	ON	ON	MCU extension mode 0
		OFF	MCU extension mode 1
	OFF	ON	MCU extension mode 2
		OFF	Single chip mode
OFF	ON	ON	Boot mode
		OFF	User Boot mode
	OFF	ON	User Programming mode
4:ON FLASH WRITE PROTECT 4:OFF FLASH UNLOCK			

CHANGE	Ver. 1.0			RENESAS SOLUTIONS CORPORATION				M3A-HS86
		SCALE		DRAWN	CHECKED	DESIGNED	APPROVED	H-UDI/RESET/UART/POWER ( 5 / 7 )
		DATE	07-01-18					DK30504

**Extension Connector**

**NMI SWITCH CIRCUIT**

**IRQ SWITCH CIRCUIT**













**MRES SWITCH CIRCUIT**

**RENESAS SOLUTIONS CORPORATION**

**M3A-HS86**

BUS CONNECTORS/PUSH SW ( 6 / 7 )

**DK30504**



**Extension Connector**

**NMI SWITCH CIRCUIT**

**IRQ SWITCH CIRCUIT**

**MRES SWITCH CIRCUIT**






**RENEASAS SOLUTIONS CORPORATION**

**M3A-HS86**


BUS CONNECTORS/PUSH SW ( 6 / 7 )

**DK30504**

TEST PIN



AGND-GND



CHANGE	Ver. 1.0				RENESAS SOLUTIONS CORPORATION				M3A-HS86	
			SCALE		DRAWN	CHECKED	DESIGNED	APPROVED	OTHERS	( 7 / 7 )
			DATE	07-01-18					DK30504	

This is a blank page

---

SH7086 CPU Board  
M3A-HS86  
User's Manual

Publication Data    Feb. 6. 2007            Rev. 1.0

Published by            Renesas Technology Corp.  
                              Renesas Solutions Corp.

---

© 2007. Renesas Technology Corp., All rights reserved. Printed in Japan.

**SH7086 CPU Board  
M3A-HS86  
User's Manual**



**Renesas Electronics Corporation**

1753, Shimonumabe, Nakahara-ku, Kawasaki-shi, Kanagawa 211-8668 Japan

REJ10J0916-0100